# **City of Carmel** WWTP Improvements Secondary Expansion

- 10 m















Resourceful.

TERRET

Responsive. Results.





## **City of Carmel**

WWTP Improvements Secondary Expansion / Carmel, IN Project Size: \$9,884,000 / December 2019 - March 2021

The City of Carmel needed to increase plant capacity. Scope of work included the addition of (2) Aeration Tanks, a Final Clarifier, RAS Pump Station addition, Diversion Structure addition, Mixed Liquor Channel, process equipment, mechanical pipping, UV Building upgrades, and a new storm drainage system.

#### **Project Challenges**

- Inaccurate as-built drawings
- Worked closely with the Owner and Engineer to plan the complicated bypass sequence of work, while keeping plant capacity to a maximum

#### Bowen Resourceful:

 We were able to use skilled hydrovac services to locate utilities, as well as reference old drawings from the original plant project to help determine where utilities were located.

#### **Bowen Responsive:**

• Collaborating with the onsite Engineer representative, we were able to come up with a bypass sequence that accelerated the schedule and kept the plant capacity to a maximum.

#### Bowen Results:

 Had the opportunity to develop craft for upper management positions and initiated new foremen.

## **PROJECT SCOPE**

- Site Work
- Civil/Concrete Work
- Underground Piping
- Mechanical/Piping
- Equipment Setting
  - RAS Pumps (2)Peripheral Feed Clarifier Equipment
  - Peripheral Feed Clarifier Equipment
    (3) 1 New, 2 Retrofit
    UV Disinfection Equipment
- UV Disinfection Equipment
- Manual and Actuated Stainless Steel Slide Gates (18)
- Manual and Actuated Valves 6" -18" (52)
- Sanitaire Fine Bubble Aeration System (2 new systems with 1600 new pods and 2600 replacement pods for existing tanks)
- Mixers
- Sampling Equipment

## **PROJECT SPECS**

- 33,700 CY of Excavation
- 20,800 CY of Backfill
- 2,400 CY of Concrete
- 247 Tons of Rebar
- 48,900 SF of Formwork
- 1,600 LF of UG DIP (30")
  1,900 LF of PVC/HDPE
- 900 LF of FL DIP (30")
- 900 LF OT FL DIP (30 )

## **PROJECT TEAM**

- Bowen Contact: Mark Cvetkovich / Matt Lash
- Engineering: Jones and Henry Engineers, Ltd.

## **PROJECT IMAGES**



Scan the barcode with your Camera App to see images of this project.

www.bowenengineering.com

